

Federal Aid Highway Program Funding

through the

Safe Routes to School Infrastructure Program (SRTS)



SRTS Program


- Federally funded reimbursement program
- Established in August 2005
- Princeton was awarded a grant as part of the 2014 SRTS Program
- Typical Projects
 - Intersection improvements, pavement marking and signage improvements, signal upgrades, curb and sidewalk upgrades

SRTS Objectives

- Enable and encourage children grades K-8 to walk and bicycle to school
- Make bicycling and walking to school a safer and more appealing transportation alternative, thereby encouraging a healthy active lifestyle from an early age
- Facilitate the planning, development, and implementation of projects that improve safety and reduce traffic, fuel consumption, and air pollution in the vicinity of schools



Project Location Map




Existing Conditions

Harrison Street is a two-lane road that runs from Route 27 to Route 206 through Princeton. The Franklin Avenue and Hamilton Avenue intersections are approximately 0.2 miles apart. The speed limit through the project area is 25 MPH. John Witherspoon Middle School, Princeton High School, and Littlebrook School are in the vicinity of the two intersections. There are non-compliant ADA curb ramps at both Franklin Avenue and Hamilton Avenue

intersections.



Harrison Street and Franklin Avenue




Harrison Street and Hamilton Avenue


Proposed Improvements


- Mill and resurface each intersection.
- Upgrade curb ramps for ADA compliance.
- Install new above-ground traffic signal equipment including traffic signal poles, mast arms, traffic and pedestrian signal heads, push buttons, and controllers.
- Improvements will be in accordance with current MUTCD, NJDOT, and ADA standards.











Next Steps

Complete Preliminary Design
November 2016

NJDOT to Approve Environmental Document December 2016

Complete Final Design and Submit to NJDOT for Review April 2017

Anticipated Federal Authorization to Construct
May 2017

• Begin Construction * June 2017

Construction Substantially Completed * August 2017

* Subject to NJDOT Authorization

